

Clover Township – Toadtown Road



Problem: Existing ditches were saturated. There were a limited number of cross pipes, the road was entrenched and acting as a ditch. Sediment and road material were running off into the stream.

Solution: Additional crosspipes were installed with headwalls and endwalls. Turnouts were installed. The road bank was graded to increase sheet flow. The road base was built up and the road was crowned.