

Eldred Township – Greeley Road



Problem: Groundwater and a lack of cross pipes was saturating the road base. The road was entrenched and acting as a ditch.

Solution: Three cross pipes were installed. Headwalls and endwalls were installed. 1440' of under drains were installed. The road base was built up 3' to encourage sheet flow off of the road surface.

