

Summerville Borough – Broad Street



Problem: The existing double-pipe stream crossing was undersized and not functioning properly. Other existing crosspipes were also too small. There were wetland areas on both sides of road which caused the road base to be saturated and sink.

Solution: A larger, single pipe was installed at the stream crossing. Larger crosspipes were also installed throughout the project. The road base was built up after installing woven Geo Textile fabric to stabilize the road base. Underdrains were also used to help keep water from saturating the road base.

